

ILLEGIB

Approved For Release 2001/03/03 : CIA-RDP78T05439A000400380077-6

Next 2 Page(s) In Document Exempt

Approved For Release 2001/03/03 : CIA-RDP78T05439A000400380077-6

~~TOP SECRET~~

Copy 98  
17 Pages

16553  
TCS-80178/65

February 1965

PHOTOGRAPHIC INTERPRETATION REPORT

ICBM COMPLEX, UZHUR, USSR



-CIA



DIA


Handle Via **TALENT - KEYHOLE** Control Only

WARNING

Declass Review by NIMA/DoD

This document contains classified information affecting the national security of the United States within the meaning of the espionage laws, U. S. Code Title 18, Sections 793 and 794. The law prohibits its transmission or the revelation of its contents in any manner to an unauthorized person, as well as its use in any manner prejudicial to the safety or interest of the United States or for the benefit of any foreign government to the detriment of the United States. It is to be seen only by personnel especially indoctrinated and authorized to receive TALENT-KEYHOLE information. Its security must be maintained in accordance with KEYHOLE and TALENT regulations.

NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER



~~TOP SECRET~~

GROUP 1  
Excluded from automatic  
downgrading and declassification

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

PHOTOGRAPHIC INTERPRETATION REPORT

ICBM COMPLEX, UZHUR, USSR

February 1965

NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

25X1A

Launch Site A (TDI Site 1)	55-20N 89-44E
Launch Site B (TDI Site 2)	55-17N 89-38E
Launch Site C (TDI Site 3)	55-19N 89-34E
Launch Site D (TDI Site 4)	55-17N 89-27E
Launch Site E (TDI Site 5)	55-13N 89-33E
Launch Site F (TDI Site 6)	55-25N 89-30E




FIGURE 1. LOCATION OF COMPLEX.

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

### INTRODUCTION

The Uzhur ICBM Complex, located 110 nautical miles (nm) southwest of Krasnoyarsk, is situated in an area of flat-to-gently rolling terrain south, west, and northwest of the town of Uzhur (Figure 1). The general relief ranges between 1,650 and 1,950 feet and, although some agriculture is carried on in the area, much of the surrounding countryside is forested and several of the launch sites are heavily wooded.

Geologically the area is underlain by simply folded sedimentary rocks, probably sandstones and shales, which in each case are located within a relatively few feet of the surface at the launch areas.

The complex consists of a complex support facility, a rail-to-road transfer point, and 6 single-silo launch areas, all under construction. It was first identified on photography of [REDACTED]

[REDACTED] on which construction activity can be noted at the complex support facility and Launch Areas, B, D, and F. The entire complex can be negated on photography of [REDACTED]. In contrast to other known single-silo complexes, where construction equipment has been moved to the sites along unimproved existing roads or across open terrain, some effort apparently has been made at the Uzhur complex to improve existing roads leading to several of the construction sites.

All of the launch areas appear to have certain common features. Each launch site contains a square, or nearly square, excavation flanked on opposite sides by earth mounds. In most cases spoil from the excavation is

used to construct an apparently level earthen rectangle on the northwest side of the excavation, with its long axis oriented approximately on the center of the excavation. Opposite this rectangle, on the southeast side of the excavation, is a smaller nearly square area which is sometimes prepared by means of an earth cut. These rectangles and squares possibly will serve as missile-handling ramps and open silo-cover positions, respectively, when site construction is completed. Removed from each of the silo excavations, at distances varying from approximately 0.2 to 0.7 nm, is a group of buildings connected with the launch site by road or trail. This group consists, characteristically, of 2 relatively large rectangular buildings and several smaller buildings or sheds. Adjacent to the large rectangular buildings at 4 (possibly 5) of the launch areas is an additional group of 4 or 5 small aligned structures. The orientation and distances between launch areas are shown in Figure 2.

### COMPLEX SUPPORT FACILITY

The complex support facility (55-178 89-49E) adjoins the town of Uzhur on the south. It consists of a railhead and storage area, an administration area, and a number of housing or probable housing areas (Figure 3). The facility is not secured entirely, but access to certain portions has been restricted by fencing. A branch from the Achinsk-Abakan rail line serves the facility, and road service is provided by the extension and/or improvement of previously existing roads in the vicinity.

The railhead and storage area occupies [REDACTED]

- 1 -

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

25X1B  
25X1B

25X1D  
25X1D

25X1D

25X1B  
25X1B

25X1D


Approved For Release 2001/03/03 : CIA-RDP78T05439A000400380077-6

Approved For Release 2001/03/03 : CIA-RDP78T05439A000400380077-6

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65



25X1D

Railhead and Storage Area	
1 Building (U/C)	400 x 65
1 Building	315 x 65
1 Building	150 x 50
1 Building	135 x 50
1 Building	135 x 40
1 Building	130 x 45
1 Building	160 x 45
1 Building	145 x 40
3 Buildings	120 x 35
1 Building	115 x 35
1 Building	125 x 45
1 Building	125 x 40
1 Building	110 x 35
1 Building	105 x 30
1 Building	105 x 45
1 Building	95 x 45
1 Building	95 x 55
2 Buildings	45 x 35
1 Building	110 x 30

Administration Area	
1 U-shaped building	195 x 45
1 Building	135 x 40
1 Building	105 x 35
1 Building	80 x 30
2 Buildings	80 x 35
1 Building	70 x 30
1 Building	60 x 55
1 Building	55 x 40
3 Buildings	55 x 30

Housing Area	
11 Buildings	135 x 45
5 Buildings	240 x 55
1 Building	275 x 60
3 Buildings	170 x 45
1 T-shaped building	190 x 110
1 L-shaped building	160 x 135
7 Buildings	55 x 30
2 Buildings	115 x 45
2 Buildings	145 x 40
1 Building	135 x 45
1 Building	80 x 40
1 Building	90 x 45
1 Building	65 x 40
1 Building	40 x 35

Miscellaneous Buildings	
1 Building	140 x 45
1 Building	60 x 45
1 Building	65 x 40
1 Building	40 x 20
1 Building	185 x 60
1 Building	260 x 60
1 Building (U/C)	285 x 75
1 Building (U/C)	105 x 70
1 Building (U/C)	120 x 80
1 Building	50 x 20
1 Building	25 x 15
1 Building	40 x 25
1 Building	45 x 15
1 Building	55 x 20
1 Building	50 x 30
3 tanks (U/C)	140 x 45

25X1D

All dimensions are in feet

FIGURE 3. COMPLEX SUPPORT FACILITY.

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

most of the southern portion of the complex support facility. It contains 2 rail spurs and a third track which extends south and west to the rail-to-road transfer point. When completed, trackage within the area will total approximately 4,000 feet. There are 22 buildings in the area, including a very long one under construction. Security fencing is under construction around the motor pool/vehicle park in the northwest corner of the area.

The administration area, consisting of a large U-shaped building and 11 smaller build-

ings, adjoins the railhead and storage area on the southwest. Three or 4 storage tanks are under construction just south of the administration area.

The main housing area, located at the northwest extremity of the complex support facility, is enclosed by a fence (probably board). It contains 13 housing-type buildings (including 1 under construction), 8 other buildings, 14 probable tents, and 6 small shed-like structures. A probable housing area is under construction just south of the main housing



25X1D




FIGURE 4. RAIL-TO-ROAD TRANSFER POINT.

NPIC 048077 (2/65)

- 4 -

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only



# TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

area. It consists of a multistory apartment-type building and 2 others under construction, with excavations for 3 more underway. Another probable housing area, located east of the main housing area and north of the railhead and storage area, contains a large possible duplex-type building and an excavation of the same size, and 10 smaller possible single-dwelling-type buildings.

Several buildings of undetermined function, including 1 under construction and 3 in the foundation stage, are located at the western extremity of the complex support facility.

## RAIL-TO-ROAD TRANSFER POINT

A rail-to-road transfer point (Figure 4) is under construction 3.0 nm west of the complex support facility. Construction activity was first observed at the transfer point in [REDACTED] and it can be negated on photography of [REDACTED]

Clearing and grading are nearly complete, but the configuration of the transfer point is not yet well defined. The rail and road approach each other almost at a right angle, and the clearing of vegetation west of their projected intersection has been accomplished. Construction of the actual transfer facilities has not been started.

## LAUNCH AREA A

Launch Area A (Figure 5) is located 4.3 nm northwest of the complex support facility. There was no evidence of the launch area in [REDACTED] and it was first observed in a midstage of construction in [REDACTED]. The area cannot be negated on cloud-covered photography of [REDACTED]

The single-silo launch site is in a mid-

stage of construction and is enclosed by a probable security fence, and bounded on 3 sides by rising terrain. It contains an excavation about 120 by 115 feet, with a silo coring which has a diameter of approximately [REDACTED] feet. The smaller of the characteristic mounds at this site is an earth cut 150 by 70 feet, and the larger rectangular mound is a spoil pile 270 by 100 feet. The silo coring and the long axis of the rectangular mound and the center of the square mound are aligned on an azimuth of [REDACTED] degrees. A ringlike object, [REDACTED] feet in diameter, was observed on the smaller mound in [REDACTED]

There are also 5 small, probably temporary, sheds within the launch site and a probable security building near the entrance.

Approximately 2,700 feet west of the silo coring is an area of construction activity which is connected with the launch site by a graded road. It includes 2 large rectangular buildings, 1 of which is under construction, 2 buildings about 70 by 25 feet, 5 small sheds under construction, and a group of 5 aligned unidentified structures. Four of the 5 structures are evenly spaced, but the fifth is somewhat removed from the others. A probable ground scar connecting the 5 aligned structures extends along their east side--the side nearest the launch site.

## LAUNCH AREA B

Launch Area B (Figure 6) is located 6.1 nm west of the complex support facility. Construction activity was first identified in an early stage on photography of [REDACTED] and the entire launch area can be negated on photography of [REDACTED]



The single-silo launch site, containing a 110- by 105-foot excavation with a center

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

25X1D



25X1D

LAUNCH SITE	
Excavation	120' x 115'
Silo coring	120' Diameter
Graded area	150' x 70'
1 Building	70' x 35'
1 Building	45' x 25'
1 Building	40' x 20'
1 Building	35' x 25'
1 Building	30' x 30'

AUXILIARY BUILDINGS	
4 Structures	40' x 20'
1 Structure	40' x 40'
1 Building	135' x 40'
1 Building	130' x 40'
2 Buildings	70' x 25'

FIGURE 5. LAUNCH AREA A.


TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65



ILLEGIB

LAUNCH SITE		25X1D	AUXILIARY BUILDINGS	
Excavation	110 x 105		1 building	140 x 45
Silo coring	110 diameter		1 building	135 x 35
Prepared spoil pile	250 x 110		1 building	120 x 35
Graded area	65 x 50		1 building (U/C)	70 x 20
3 buildings	50 x 15 (approx)		3 structures	30 x 25
			1 building	35 x 20
			1 building	75 x 25

ALL DIMENSIONS ARE IN FEET.

FIGURE 6. LAUNCH AREA B.

- 7 -

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

25X1D coring [REDACTED] in diameter, is in a midstage of construction. Spoil has been piled on the northwest side of the excavation and, when completed, this apparently will be a rectangular graded area level with the top of the silo. Southeast of the excavation is a smaller, more nearly square graded area. The long axis of the spoil pile, the silo excavation, and the center of the squared area are oriented on an azimuth of [REDACTED]. Three buildings, probably related to construction activity, are located near the excavation. No security fencing has been identified at this launch site as yet.

25X1D Approximately 1,000 feet west of the silo coring is a long, narrow excavation with an unidentified piece of equipment along its southern side and a spoil pile just to the east of it. Track activity connects the excavation with the launch site, and ground scarring extends to a building approximately 600 feet to the west.

A group of 2 large rectangular buildings and several smaller structures under construction is located approximately 1,900 feet west of the launch site. A similar pair of buildings and associated structures can be seen at each of the other launch areas of the Uzhur complex, and at each of the launch areas at the Aleysk and Dombarovskiy complexes. Although build-

25X1B



A faint trail leads 1,300 feet west from the vicinity of the rectangular buildings to a fenced compound with a single building near its center. Although construction of this compound was the first activity identified at Launch Area B, its function has not been determined.

Approximately 3,000 feet northwest of the launch site is a possible mast situated in a clearing on the side of a hill. Track activity

extends to the southeast approximately 1,300 feet from the clearing to connect with the launch site access road.

#### LAUNCH AREA C

Launch Area C (Figure 7) is located 9.0 nm west-northwest of the complex support facility. There was no evidence of the launch area in [REDACTED] and it was first observed in a very early stage of construction in [REDACTED]. The area was cloud covered on earlier photography in [REDACTED] but had progressed to a midstage of construction by [REDACTED].

The terrain slopes generally upward on 3 sides of the nearly square single-silo launch site, which is enclosed by a security fence approximately 900 feet on a side. The silo excavation, smallest of those at the Uzhur complex, is approximately 70 by 60 feet and contains a coring approximately [REDACTED] in diameter. The characteristic rectangle and square on either side of the excavation are cuts into the sloping terrain rather than spoil piles. The smaller area is 120 feet square, and the larger 270 by 105 feet. There is 1 shed-type building within the launch site, and a probable building 35 by 20 feet near the entrance.

An area of construction activity 4,200 feet east of the launch site contains the characteristic 2 large rectangular buildings, 1 of which is under construction. Nearby are 6 unidentified structures, 5 of which have an alignment resembling a similar group of structures at Launch Area A. The sixth structure at Launch Area C has a different configuration than the others, and is not connected with the others by the probable ground scar extending along their west side--the side nearest the launch site.

25X1D

25X1D

25X1D

25X1D

25X1D

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
Talent Keyhole  
Control System Only




FIGURE 7. LAUNCH AREA C.

ILLEGIB

Handle Via  
Talent Keyhole  
Control System Only

TOP SECRET RUFF

ICS-80178/65

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

#### LAUNCH AREA D

Launch Area D (Figure 8) is located 13.0 nm west of the complex support facility. Construction activity was first identified in an early stage in [REDACTED] and the area can be negated on photography of [REDACTED]

[REDACTED] the silo excavation had not been started, but initial construction of buildings was underway. The launch area was cloud covered on photography of [REDACTED] and [REDACTED] and construction of the silo excavation was first observed in [REDACTED]. The launch site is in a midstage of construction on the latest usable coverage of the area in [REDACTED]

The single-silo launch site is situated in a small clearing adjacent to a dirt road. No security fencing has been identified. The silo excavation is approximately 140 by 115 feet, with a coring approximately [REDACTED] feet in diameter. The characteristic graded square mound is evident southeast of the excavation, but the rectangular mound is only a partially formed spoil pile northwest of the excavation. The square mound and the silo coring are oriented on an azimuth of [REDACTED]. There are 2 small buildings, 1 adjacent to a scarred area, northeast of the silo coring and near the site access road.

Approximately 4,400 feet north-northeast of the launch site, on the west side of the access road, are 3 buildings, a probable lattice tower, and an unidentified object. The 2 characteristic large rectangular buildings are included among the 3, but the associated group of aligned structures observed at Launch Areas A and C is not present at this launch area.

#### LAUNCH AREA E

Launch Area E (Figure 9) is located 10.2

nm southwest of the complex support facility. Construction activity was first identified in an early stage in [REDACTED] when the silo excavation and coring were evident. There was no evidence of the launch area on photography of [REDACTED]

The single-silo launch site, enclosed by a security fence with sides 1,230, 1,060, 1,045, and 955 feet long, is in a midstage of construction. The silo excavation is approximately 140 by 115 feet, with a coring approximately [REDACTED] in diameter. The large rectangle on the northwest side of the excavation appears to be an earth cut, and the small flat-topped, nearly square, mound on the southeast side has been constructed of spoil from the excavation. The silo coring and the long axis of the rectangle are oriented on an azimuth of [REDACTED]. Only 1 possible building is located within the launch site, about 300 feet southwest of the excavation.

A partly fenced area of construction activity approximately 4,000 feet northeast of the launch site contains 1 large rectangular building, 1 probable rectangular building, a smaller building, and several unidentified structures. Monoscopic coverage of this area in [REDACTED] revealed 4 small sheds or mound-like objects aligned near the east side of the security fence. This alignment, similar to that observed in association with the 2 large rectangular buildings at Launch Areas A and C, is not apparent on the most recent coverage of Launch Area E in [REDACTED]

North of the partly fenced area is an L-shaped clearing containing what appears to be an earth mound approximately [REDACTED] in diameter, with a possible mast at its center.


TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

FCS-80178/65



**LAUNCH SITE**  
Excavation  
Silo coring  
Graded area  
1 Building

140' x 115'  
Diameter  
95' x 95'  
65' x 30'

25X1D

**AUXILIARY BUILDINGS**  
1 Building 140' x 45'  
1 Building 130' x 50'  
1 Building 60' x 40'

FIGURE 8. LAUNCH AREA D.

- 11 -


TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65



ILLEGIB

LAUNCH SITE		25X1D	AUXILIARY BUILDINGS	
Excavation	140' x 115'		1 Probable building	120' x 40'
Silo coring	135' x 95'		1 Building	130' x 40'
Graded area	90' x 85'		1 Building	60' x 40'
Spoil pile			1 Structure	40' x 20'
			1 Structure	25' x 15'

FIGURE 9. LAUNCH AREA E.

TOP SECRET RUFF


Handle Via  
TALENT-KEYHOLE  
Control System Only



Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

TCS-80178/65



LAUNCH SITE

Excavation	180' x 145'
Silo coring	180' Diameter
Spoil pile	240' x 125'
Spoil pile	110' x 100'
1 Building	75' x 35'
1 Structure	30' x 30'

25X1D

AUXILIARY BUILDINGS 25X1D

1 Building (U/C)	140' x 45'
1 Building	140' x 40'
2 Structures	30' x 30'
1 Building	75' x 25'
1 Clearing	50' x 45'

FIGURE 10. LAUNCH AREA F.

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

ICS-80178/65

LAUNCH AREA F 25X1D

25X1D Launch Area F (Figure 10) is located 9.2  
25X1D nm northwest of the complex support facility.  
The launch area was first identified in an  
early stage of construction in [REDACTED]  
[REDACTED] and it can be negated on  
photography of [REDACTED]

25X1D The single-silo launch site, partly enclosed  
by a possible security fence, is in a midstage  
of construction. The silo excavation, approx-  
imately 150 by 145 feet, contains a coring  
about [REDACTED] in diameter. The characteristic  
rectangular and square mounds on either side  
of the excavation consist of spoil at this launch  
site. The long axis of the rectangular mound,  
the silo coring, and the center of the square  
25X1D mound are oriented on an azimuth of [REDACTED]  
degrees. A clearing containing a roughly  
cross-shaped, dark-toned object of undeter-  
mined function is just northeast of the ex-  
cavation. A number of small construction-  
type buildings are also located near the launch  
site.

A group of buildings similar in appearance  
to those seen at the other launch areas of  
the complex is under construction approximately  
2,700 feet south-southeast of the launch site.  
Included in the group are 2 large rectangular  
buildings (1 under construction) oriented at an  
approximate right angle, and 2 small square  
structures aligned with a narrow rectangular  
building. On photography of [REDACTED]

25X1D [REDACTED] 2 additional small square un-  
25X1D identified structures were located where the  
narrow rectangular building now appears, in-  
dicating that the larger building is constructed  
over and connecting the smaller structures.  
Another narrow rectangular building may be  
expected to cover and connect the 2 remain-  
ing small square structures. This config-  
uration would differ from those at the other  
launch areas of the Uzhur complex, but would  
be very similar to those at the Dombarovskiy  
complex.

The significance of the large borrow pit  
approximately 0.6 nm east-southeast of the  
silo excavation has not been determined.

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

TOP SECRET RUFF


Handle Via  
TALENT-KEYHOLE  
Control System Only

TCS-80178/65

REFERENCES

25X1D

PHOTOGRAPHY



MAPS OR CHARTS

SAC. US Air Target Chart, Series 200, Sheet 0161-4HL, 2d ed, Nov 61, scale 1:200,000 (SECRET)

REQUIREMENT

GMAIC. 28-64

NPIC PROJECT

11781 64

- 15 -

TOP SECRET RUFF

Handle Via  
TALENT-KEYHOLE  
Control System Only

25X1D

Approved For Release 2001/03/03 : CIA-RDP78T05439A000400380077-6

Approved For Release 2001/03/03 : CIA-RDP78T05439A000400380077-6